

City of San Jose Del Monte, Bulacan
REQUEST FOR QUOTATION

TEL NO.:

[illegible]

Date

SAN JOSE DEL MONTE CITY WATER DISTRICT

TECHNICAL SERVICE UNIT

PROPOSED INSTALLATION OF ENCLOSURE FOR DISMANTLED STEEL TANK (DEBRIS) AT VACANT LOT BESIDE SPTP - GI CORR. ROOF IN STEEL FRAMING

Road 1 - Industrial Road, Minuyan Proper, City of San Jose Del Monte, Bulacan

Stations:

Length:

| ITEM NO. | DESCRIPTION | QTY | UNIT |
|-----------|--|--------|-------|
| (1) | (2) | (3) | (4) |
| A. | MATERIALS | | |
| 1 | Cement | 2.00 | bags |
| 2 | Sand | 0.25 | cu.m. |
| 3 | Gravel 3/4 | 0.25 | cu.m. |
| 6 | Tie Wire #16 | 5.00 | kgs. |
| 8 | GI Corr. Roof, 6ft. Ga 26 | 63.00 | pcs. |
| 9 | Tubular, 1 1/2"x1 1/2"x1.5mm | 30.00 | pcs. |
| 10 | Texscrew, 1 1/2" | 944.96 | pcs. |
| 15 | Welding Rod | 1.00 | box |
| 16 | Cutting Disc | 5.00 | pcs. |
| 17 | Grinding Disc | 3.00 | pcs. |
| 18 | Lockset (Padlock & Steel Chain) | 1.00 | set |
| 12 | Cylindrical Hinges, 1" | 2.00 | pcs. |
| 20 | QDE Paint/Primer | 2.00 | gal |
| 21 | Lacquer Thinner | 2.00 | gal |
| 22 | Paint Brush, 2" | 2.00 | pcs. |
| 23 | Sand Paper | 5.00 | pcs. |
| | | | |
| | | | |
| B. | EQUIPMENT | | |
| 1 | Welding Machine | 3.00 | days |
| 2 | Genset | 3.00 | days |
| | | | |
| | | | |
| | | | |
| C. | LABOR | | |
| | Clearing & Grubbing | 1.00 | lot |
| | Layout & Staking | 1.00 | lot |
| | Hauling of Materials (Huddle/Collecting other debris/materials Together) | 1.00 | lot |
| | Excavation & Backfilling | 0.19 | cu.m. |
| | Concrete Pouring | 0.19 | cu.m. |
| | Installation of Steel Frames & GI Pre-Painted Roof | 1.00 | lot |
| | | | |
| | | | |
| | | | |
| | | | |